# DFC - QK BUILDING - 1105 & 1105B DRAWING VENUE CHAIR & DESK INSTALLATION

NOTE:
- ALL WORK TO BE DONE AS PER SPECIFICATION
- MAKE GOOD ALL WORK
- ALL WORK TO APPROVAL
- CLARIFY ANY UNCERTAINTY
- DIMENSIONS TO BE CHECKED ON SITE

NEW WORK

DEMOLISH

Ⓐ - REMOVE EXISTING BRICKWALL /DRYWALL PANEL IN POSITION AS SHOWN AND MAKE GOOD TO APPROVAL.

① - INSTALL NEW STANDARD ALUMINIUM FRAMED SEMI-SOLID PANEL DOOR AND IRONMONGERY WITH (Key and lock specifications to be CISA cylinders with G96D keyway only) IN POSITION AS SHOWN TO MATCH EXISTING AS PER SPEC. & TO APPROVAL.

## TABLE NOTES:

- **Both sides laminated wooden board**
- **Metal/stainless steel stand with adjustable height and angles**
- **0-180 ° working angle**
- **With fitted parallel Motion and Triangle for drawing vertical and horizontal lines and angles**
- **The height of the stand is adjustable from 800mm to 1100mm**
- **Tables to be fixed to the floor.**

## CHAIR NOTES:

- **Seat made from steel 280mm diameter. Frame is made from 25mm round tubing cold rolled steel with 1.6mm wall thickness, 10mm round bar support between legs.**

500 625 500 625 500 625 500 625

863 500 863 500 863 500

SCREEN

1130

1845

1246

1499

1500

1965

1876

1351

600 Existing Lectern

1000

95 Seater

1105B
Drawing Hall
233.79m²

62 Seater

1105
Drawing Hall
163.35m²

1842

1268

2183

Existing Lectern 600

1005

| | | | |
|---|---|---|---|
| DRAWN: KC | | CAMPUS CODE: DFC | DATE: 5/3/2023 |
| APPROVED: GJ | | TITLE: DFC - QK BUILDING - 1105 & 1105B DRAWING VENUE CHAIR & DESK INSTALLATION | BUILDING: QK_BUILDING |
| CHECKED: GJ | 25/05/2023 HoD: Prof M Mashinini | | FLOOR: 1ST |

| REV | APPROVED | DATE | DESCRIPTION |
|---|---|---|---|

UNIVERSITY OF JOHANNESBURG
CENTRAL TECHNICAL SERVICES
TEL : 559-3019 FAX : 559-3206

SCALE: SCALE

DRAWING NAME: DFC - 770 - PERSKOR 01

REVISION: B